


**J-PARC accelerator complex and facilities**

**Introduction of the  
J-PARC Accelerator Complex**


Masashi Shirakata (Accelerator Laboratory, KEK)

J-PARC accelerator group








# LINAC



**LINAC beam energy: 181 MeV at the present**




Ion source, LEBT, RFQ,  
MEBT(2 choppers, 2 bunchers)



- Particle  
H<sup>-</sup> (Negative hydrogen)
- Energy  
on day-one      **181 MeV**  
with ACS      400 MeV
- Peak current  
at 181 MeV      **30 mA**  
at 400 MeV      50 mA
- Repetition      25 Hz
- Pulse width      0.5 msec

# Ion Source



Cross sectional view of J-PARC Ion source


## J-PARC Ion Source

- \*Plasma production :  
Arc discharge (LaB<sub>6</sub> filament)
- \*Number of filament : 1
- \*Cesium : free
- \*Beam aperture : 9mm diam.

**Ion : H- (Negative hydrogen)**

### Voltage among electrodes

Ground  
| - 42 kV  
Extraction  
| - 8 kV  
Plasma






# Specification of ion source

Parameters	Present source	Requirement	
		#1 stage source	1MW source
H- current [mA]	~35	~36	~60
Duty factor [%]	0.875	1.25	1.25
Pulse length [ $\mu$ s]	350 (arc)	500	500
Repetition rate [Hz]	25 (arc)	25	25
Continuous operation time [h]	157*	500	500

\*After 157 h operation, beam current decreased from 35mA to 5mA by request of beam commissioning task.



Beam current vs. arc current  
for various filament diameter

## Issues of ion source for #1 stage source:

-> Demonstration of 500 h continuous operation at 36 mA has not been yet.

## for 1MW source

-> Enhancement of the peak H- current is needed.

### \*Strategy


- Improvement of the present source (filament shape, electrode material, and so on)
- Development of new type source (cesium seeded type, RF discharge, and so on)

Marginal man power for the R&D.

Example of R&D result for  
beam current improvement

# RF System: Klystron


- 20-unit of klystrons have been operated for 8,470 hours. (from 2006 Oct. to 2009 Jan.)
- There are no serious troubles, such as a discharge in e-gun, vacuum degradation, arcing in output window.



324MHz Klystron (E3740A)

Peak Power	2.5 (max. 3.0) MW
Pulse Width	650 $\mu$ s
Repetition	50 Hz (25 Hz)
$\mu$ -Perveance	1.37 A/V <sup>3/2</sup>
Gain	50 dB
Efficiency	55 %
Beam Voltage	105 (max. 110) kV
Beam Current	45 (max. 50) A
Mounting Position	Horizontal
No of Klystron	23 = 20 + 3 (spare)

# Ion source status in the last one year



Operation history of ion source  
(May-2008 ~ Feb-2009)

## Remarks

(during beam commissioning)

24 hours continuous beam operation has started from RUN#15.

Beam operation without ion source operator has started from RUN#15 (only in night time).

On 28th June, 2008 (during RUN#17), filament had a trouble of cutting off. The filament was used in 9 commissioning runs (2030 h).

The typical beam current is set to 5 mA for the MLF experiments and MR commissioning.




# Discharge problem in the RFQ

- The first severe discharge problem in the RFQ occurred in September 2008.
- Before this problem, the availability of linac was more than 90 %.
- After the problem, we are suffering from sporadic unscheduled shutdown due to discharge problem in RFQ.
- A run cycle scheduled in Oct. 2008 was cancelled for RFQ conditioning.
- The RFQ downtime (both scheduled and unscheduled) dominated the machine time in runs in Dec. 2008 and Jan. 2009.



“RFQ backup group” has been organized, who prepares the “backup RFQ” though it takes about one year.



Inside view of RFQ

RFQ (Radio Frequency Quadrupole) uses electric quadrupole field for beam focusing. Discharge may occur at the surface with high voltage potential.



# Present Status of LINAC

## General

- The linac and RCS have been commissioned successfully.
- The stability of linac beam is sufficiently good for beam commissioning of RCS, MLF, and MR. (except for the following problem...)
- Availability and beam power is limited by mainly RFQ at the present.
- We decided to temporarily limit the beam power to 1.2 kW (corresponds to 20 kW RCS beam) in order to ease the RFQ discharge problem.

## For the high intensity

- Ion source and RFQ must be upgraded for 1 MW beam power of RCS.
- The construction of 200 to 400MeV part (Annular Coupled Structure) of the linac was funded through the supplementary budget of JFY2008.
- Design and construction of ACS is still going on.
- Installation of ACS modules is scheduled on January to March, 2011.

# RCS (Rapid Cycling Synchrotron)

1st arc section



Neutron/Muon source and booster of the MR.

Two beam transport lines:


3NBT transport line to the MLF

3-50BT transport line to the MR

Circumference 348 m  
Repetition rate 25 Hz  
Injection energy 181/400 MeV  
Extraction energy 3 GeV  
Harmonic number 2

3NBT → MLF  
3-50BT → MR


from  
Linac



Injection section



RF section



to MLF

to MR

RCS  
ring

Extraction section



# Recent runs and operations

## (1) Run#16 (May 13~June 2, 2008)

- Tuning and study for the transverse beam painting
- Startup of the beam delivery to MLF and MR for their beam commissioning  
(5 mA peak/0.1 ms long/280 ns intermediate pulse width/1 bunch; 5 kW eq.)

## (2) Run#17 (June 12~30)

- Tuning and study for the transverse and longitudinal beam painting
- Beam delivery to MLF and MR (5 mA/0.1 ms/280 ns/1 bunch; 5 kW eq.)

## (3) Run#18 (September 11~29)

- Tuning and study for the transverse and longitudinal beam painting
- High-intensity demonstrations (10-15 mA/0.5 ms/560 ns/2 bunches; 200-300 kW eq.)
- High-power demonstration (15 mA/0.5 ms/420 ns/2 bunches/25 Hz; 225 kW)
- Beam delivery to MLF (5 mA/0.1 ms/280 ns/1 bunch; 5 kW eq.)

## (4) Run#19 (November 3) Suspended due to RFQ trouble

## (5) Run#20 (December 2~26)

- High-power demonstration (5 mA/0.5 ms/560 ns/2 bunches/25 Hz; 100 kW)
- 25 Hz stable beam operation (Startup of user runs at MLF)
  - \* MLF 5 mA/0.4-0.1 ms/280 ns/1 bunch/25 Hz; 20-5 kW
  - \* MR 5 mA/0.1 ms/140-280 ns/1 bunch/single shot or 0.16 Hz

## (6) Run#21 - #24 (January 13~June 1, 2009)

- 25 Hz stable beam operation
  - \* MLF 5 mA/0.1 ms/560 ns/2 bunches/25 Hz; 20 kW
  - \* MR 5 mA/0.1 ms/140-280 ns/1 bunch/single shot or 0.16 Hz

# Transverse painting

In order to reduce the **space charge force**, artificial **off-center injection** scheme (**painting**) was tested with paint-bump system for both horizontal and vertical plane.


When the beam profile had a **broad shape**, space charge force is eased. As a result, beam loss gets smaller.

## Beam parameter


5 mA peak, 0.5 ms long,  
560 ns intermediate-pulse width

Mountain plot of the beam profile measured by IPM for the transverse painting injection

Horizontal




Vertical






# Longitudinal painting

- Only Fundamental -



- 2nd harmonics: 80% -



## Beam parameter

10 mA peak, 0.5 ms long,  
560 ns intermediate-pulse width,  
2 bunches  
\* Vmax: 402 kV/turn (with 10 cavities)  
\* Phase FB on

In the longitudinal painting, the RF frequency and the phase of **second harmonic RF** voltage are varied during injection.

Figure shows mountain plots and the bunching factors w/w.o longitudinal painting.

Momentum offset: -0.2%




Phase sweep of 2nd harmonics:  
-80 to 0 degree



**200 kW** output was achieved !

# High intensity demonstrations

- On 18<sup>th</sup> September of 2008, the highest beam power of **0.21 MW ( $1.77 \times 10^{13}$  ppp)** was demonstrated for **70 seconds**.
- Note that duration of 70 seconds was limited by the authorized beam dump capacity at that time.
- The beam loss was about 3 %.






## High intensity demonstrations cont.

15 mA peak, 0.5 ms long, 560-600 ns intermediate-pulse width, 2 bunches


Transverse painting ;  $150\pi$  correlate both for H & V



# Availability

	RUN20 (94:00)		RUN21(310:00)		RUN22(454:00)		Total (858:00)	
	Counts	Stop Time	Counts	Stop Time	Counts	Stop Time	Counts	Stop Time
Control	0	0:00:00	1	0:00:00	13	0:00:00	25	0:00:00
RF	1	0:09:38	1	0:06:00	2	0:14:44	4	0:30:22
BM	0	0:00:00	1	20:16:46	2	30:38:48	3	50:55:34
QM	0	0:00:00	0	0:00:00	0	0:00:00	0	0:00:00
STM	0	0:00:00	0	0:00:00	0	0:00:00	0	0:00:00
SB,PB	0	0:00:00	0	0:00:00	5	1:15:32	5	1:15:32
DCMAG	0	0:00:00	0	0:00:00	0	0:00:00	0	0:00:00
KM	7	2:29:34	69	16:23:48	68	13:51:24	141	32:44:46
BeamLoss	2	0:00:00	11	0:06:04	19	0:11:04	32	0:17:08
Total	10	2:39:12	83	36:52:38	107	46:11:32	210	85:43:22

## Breakdown of failures



## Availability for user operation : 90.0 %

Failures were mainly caused as follows

RF : "OC/UV" interlock of the screen grid ,  
anode and/or control grid dc-power supply.

KM : pre-fire of thyatron for extraction kicker magnet.

SB, PB : power supply was down by the noise.  
This noise happened  
when BM power supply was down.

BM : troubles

# Present Status of RCS


The RCS have been commissioned successfully.

- The optics measurement and its correction were successfully performed.
- **Transverse and longitudinal painting injections** were well-demonstrated.
- It was confirmed that the beam loss at the early stage of acceleration was well-improved by the **painting injection** scheme especially in the longitudinal plane for **200-300 kW**-equivalent intensity beam.
- **Consecutive 100 kW** (for 1 hour to MLF) and **213 kW** (for 70 s to 3NBT dump) output operations at 25 Hz were well demonstrated.
- **Stable beam operations** for **MLF (user run)** and also **MR commissioning** have been performed with **20 kW** output beam power **since December 2008**.
- For higher beam intensity, commissioning and study will continue...



# MR (slow cycling Main Ring synchrotron)

Circumference	1567.5 m
Repetition rate	~ 0.3 Hz
Injection energy	3 GeV
Extraction energy	30 GeV
Superperiodicity	3
harmonic #	9
No of bunches	8
Transition $\gamma_0$	j 31.7
Typical tune	(22.4, 20.8)
Transverse emittance	
At injection	~54 $\pi$ mm mrad
At extraction	~10 $\pi$ mm mrad (30 GeV)



Three dispersion free straight sections of 116-m long:

- Injection and collimator systems
- Slow extraction (SX)

to **Hadron experimental Hall** (Rare decay, hyper nucleus..)

- Rf cavities and Fast extraction (FX) (beam is extracted inside/outside of the ring)  
outside: Beam abort line

inside: **Neutrino beamline** (intense  $\nu$  beam is send to SK located 300 km west)

# MR beam commissioning schedule

**1st stage** (May - June 2008)

**Available beam dump: at the injection.**

Beam transport in 3-50 BT, injection, closed orbit, rf capture, extraction to beam dump at **3 GeV**.

**Installation of FX and SX components**  
(July 2008-Nov. 2008)

FX septa (SM1,2, SM33), FX kickers, SX devices, neutrino beamline components, tuning of main magnet power supplies.

**2nd stage** (Dec. 2008 - Feb. 2009)


**Available beam dump: at the abort beamline and HD beamline.**

Acceleration **from 3 to 30 GeV**, extraction to abort line, extraction to **hadron** beamline.

**3rd stage** (April - June 2009)


**Available beam dump: at the NU beamline.**

Extraction to **neutrino** beamline.




**We've just completed !!**

# 3-50 Beam Transport Line




Pulsed bending magnet

Length	230 m
Dipole	1 (pb), 3 (h), 2 (v)
Quadrupole	38
Steering	14
Collimator	12 units (120 - 54 $\pi$ mm mrad)
Monitor	
BPM / MWPM	14 / 5 (9)
FCT / BLM	5 / 50



BT collimators



Slope section



# Magnet system

## Main magnets

<b>Dipole</b>	96
<b>Quadrupole (11 families)</b>	216
<b>Sextupole (3 families)</b>	72

## Steering magnets

<b>Hori. Steerings</b>	92
<b>Vert. Steerings</b>	93
<b>Abort Steering</b>	1



Precise alignment of all the main magnets was completed in 2007.

Hardware commissioning of the main and steering magnet systems started in December 2007 as scheduled.

The total harmonics distortion (THD) of AC voltage  $\sim 1\%$  with a harmonic filter of 6.5 Mvar unit when all the power supplies operated in 30 GeV.



Injection kickers




Ring collimators

## Injection devices




Injection Line



Injection Septa



Injection dump septa



Injection dump line



# MA loaded rf cavity

The MA (magnetic alloy) cut core is adopted to the MR cavity.

At initial operation in the second stage of commissioning, required rf voltage is ~ 160 kV for 30 GeV (Nominal voltage is 40 kV/cavity).

## Long-term high power operation test of MA cores

All 90 cores (for 5 cavities) have been tested > 300 hrs with nominal rf gap voltage of 15 kVp with 60% duty.



Serious core damages have not been observed.

For the first stage of beam commissioning, four cavities have been installed.

Hardware commissioning started in March 2007.


The fifth cavity will be installed in summer 2009.






# Beam monitors

BPM	186
Abort/dump BPM	2+2
WCM (>100 MHz)	3
FCT (~ 20 MHz)	6
DCCT(DC - 30 kHz)	2
MWPM	1(inj.) + 1(SX) + 1(abort)
FWPM(H/V)	1 / 0
IPM(H/V)	1 / 1
Tune meter (H/V)	1 / 1
Quad. mode BPM	2
BPM (BT)	14
FCT (BT)	5
MWPM (BT)	6
BLM(BT&MR)	338



Installation, cabling and calibration still continue.



# Beam Commissioning

## Procedure

### 1st stage: Injection and 3 GeV DC

- 3-50BT orbit correction
- Injection tuning
- COD correction
- Closed orbit establishment
- RF capture
- $\eta$ -function measurement
- $\beta$ -function measurement
- Tune measurement & survey
- Optimization of operating point
- RF parameter tuning
- Chromaticity correction

} Iterate while necessary

Ring parameter measurement

### 2nd stage: Acceleration

- Acceleration
- Optimization process same as above
- FX devices tuning
- Confirmation of adiabatic damping

## Linac/RCS beam for MR commissioning

Linac: 5 mA, 100  $\mu$ sec, chopped beam  
RCS: without painting,  
~10  $\pi$  mm mrad  
one bunch operation ( $h=2$ )  
< 4e11 ppb (1 % intensity),  
single shot


### Beam extraction to HD beamline

- Establish optimum operating point
- Tune Survey
- Physical aperture survey
- Dynamic aperture survey
- Beam extraction tuning
- HD beamline tuning
- SX devices tuning
- Spill control (Sep. 2009 ~)

### Beam extraction to NU beamline

- Establish optimum operating point
- Beam extraction tuning
- NU beamline tuning


# Orbit correction in the 3-50BT





# Injection Tuning 1

## Injection beam envelope and layout of the components



### Tunable knobs

#### Ring

Septum1, 2  
kicker1, 2, 3

#### 3-50BT

zsh09, 10  
zsv11, 12


Bump magnets are installed to make a local bump to secure the large physical aperture for the circulating beam. But we **did not use** the **local bump** in the 1st stage because of the small beam size.

Discrepancies from the design are small.

# Injection Tuning 2


**BPM: Turn-by-turn mode**

Before



↓ Injection error was well suppressed.

After





# COD Correction

## BPM: COD mode

In COD mode, BPM measures the averaged position of the beam.

**Amplitude of orbit distortions was suppressed!**




**Orbit analysis  
&  
Correction by steering  
magnets**



# RF Capture

Mountain plot of longitudinal beam profile measured by WCM




$$f_{\text{rf}} = 1.6715 \text{ MHz}$$

$$V_{\text{rf}} = 160 \text{ kV}$$

The frequency is well matched and no dipole oscillation is observed.

Matching between field of dipole magnet and RF frequency


1000 turn mode:  
Beam is extracted after 1000 turns from the injection.



# $\eta$ -function Measurement


The  $\Delta p/p$  dependence of the closed orbit is measured by changing RF frequency.

Time pattern of RF frequency change



$$\Delta x = \eta_x \Delta p/p$$



RF shifts the beam momentum.  
Beam orbit represents the  $\eta$  -function.



Measured results agree well with design.

# $\beta$ -function Measurement

- We measured  $\beta$  -function using the relation:  $\beta \Delta k \rightarrow \Delta \nu$   
Averaged  $\beta$  at the position of each Q families
- Measurement error :  $\Delta \beta / \beta \sim 10 \%$ .



Measured results agree with the designs within the measurement error.



# Tune and Resonance

- Particles in beam oscillates with a characteristic frequencies both in horizontal and vertical planes. These are called tune:  $\nu_x$  and  $\nu_y$ , respectively.
- When the error field existed, particles are affected periodically. When the particle motion is synchronized to the affection, the amplitude of particle motion gets larger. (This is called as the “resonance”)
- Resonance conditions can be expressed in the **tune diagram** which is a 2D plot of  $\nu_x$  and  $\nu_y$ .

- Strength of resonances

Resonant condition:  $m\nu_x + n\nu_y = k$

$\nu_x$  : horizontal tune,  $\nu_y$  : vertical tune

$m, n, k$  are integers.

(  $|m| + |n|$  ): order of resonance; Low order resonances are strong and harmful.

- Expected resonances (example)

$\nu_x = 22$  (integral resonance: very strong)





$2\nu_x = 45$  (half-integral resonance: very strong)

$\nu_x + \nu_y = 43$  (sum resonance: strong)

$\nu_x = 22.333$  ( $3\nu_x = 67$ , third order resonance used in slow extraction)

$\nu_x + 2\nu_y = 64$

# Tune Survey





$v_x = 22$

$2v_x = 45$

$2v_x + v_y = 43$




# Fast extraction devices

Fast extraction system comprises 5 bipolar kicker magnets and 8 bipolar septum magnet systems.







# Lumped constant kicker magnet



Vacuum chambers and ferrite cores of the traveling type kickers are used.  
The maximum voltage between coil and ferrite cores is  $<1.5$  kV/mm.

# Fast extraction septum magnets



SM30-32 were Installed in the ring tunnel before the first MR beam.  
SM33, SM1,2 were installed in summer of 2008.



# Abort beam line

Abort beam is bent outward in the fast extraction section and transported to 7.5 kW dump.

- Beamline length ~ 73 m
- DC Q-doublet is installed at 10 m from the extraction point.



**Quadrupole (recycled)**



**DC PS (recycled)**



**φ 746 Beam duct**

The abort beamline components was installed in summer of 2008.



# Slow extraction system

Installed before the first MR beam

Resonant Sextupole (8)

Manufactured in 2007,  
installed in summer of 2008

Electro-static septum (2)

Thin septum magnets:

1.5 mm (1), 3.5 mm (1), 7.5 mm (4)


Strong field septum magnets (4)

Shift bump magnet (4)


Power supplies (recycled/manufactured)

Manufactured in 2007-2008,  
to be installed in summer of 2009

Extraction Q's for spill control



Resonant sextupoles




Vacuum vessel of ESS



Yoke and 30μm ribbon type septum of ESS

Details are given by M. Tomizawa

# Slow Extraction procedure




Turn off the RF



coasting beam without RF  
binding force (DC beam)



move to  $\nu_x = 22.333$  and enhance the resonance




Particle motion becomes unstable  
due to the resonance.

peel off the spilled  
particles


# Beam peeling in Electro Static Septum

Observed beam  
by the luminescence  
screen monitor



Extracted  
spill

shadow  
of ribbons




Inside view of ESS



# Observed Beam Spill

**Beam spot can be observed in some luminescence screen monitors in hadron beam line.**



**It was confirmed that more than 90% beam was extracted.**

# Present status of MR

Installation of accelerator components is now in progress **as schedule.**

Off beam commissioning has started in December 2007.

Beam commissioning has started in May 2008.

**1st stage (May - June 2008)**

**3 GeV** DC operation

**2nd stage (Dec. 2007- Feb. 2008)**

Acceleration to **30 GeV**

Beam extraction to the abort dump and **hadron** beamline

**3rd stage (April - June 2009)**

Beam extraction to **neutrino** beamline

**The first mission has been COMPLETED !!**


# Milestones

- Linac Beam Commissioning started in Nov, 2006.
- The linac accelerated the beam to a design value, 181 MeV on 24th Jan, 2007.
- RCS Beam Commissioning started in Oct., 2007.
- The RCS accelerated the beam to a design value, 3 GeV on 31st Oct, 2007.
- Beam Commissioning of MR started in May, 2008.
- Installation of FX and SX components were installed in summer, 2008.
- Hadron and Neutrino beamline components were installed in summer, 2008.
- MLF experiments started on 23rd Dec, 2008.
- The MR accelerated the beam to a design value, 30 GeV on 23rd Dec, 2009.
- Extraction to hadron beamline on 27th Jan, 2009.
- Secondary beam was confirmed 11th Feb, 2009.
- Extraction to neutrino beamline on 23rd April, 2009.
- Neutrino beam was confirmed 23rd April, 2009.



# Present status of MLF




Since 30th May, 2008




## Available beam lines:

- BL01** 4D space access neutron spectrometer (4 SEASONS)
- BL03** IBARAKI Biological Crystal Diffractometer (iBIX)
- BL04** Neutron-Nucleus Reaction Instrument (NNRI)
- BL08** Super high resolution powder diffractometer (SuperHRPD)
- BL10** NeutronBeam-line for Observation and Research Use (NOBORU)
- BL14** Cold-neutron disk-chopper spectrometer (AMATERAS)
- BL16** High-Performance Neutron Reflectometer with a Horizontal Sample Geometry (ARISA-II)
- BL19** Engineering Diffractometer (TAKUMI)
- BL20** IBARAKI Materials Design Diffractometer (iMATERIA)
- D1** D1 instrument (Muon beam line)

# Observation of the neutrino beam production



**Muon Monitor and its first muon signal.**





**Superconducting bending magnets**





# Identification of kaons

Joint experimental team, E17 lead by Prof. R. Hayano, University of Tokyo and E15, lead by Dr. M. Iwasaki, Riken, has successfully confirmed **kaon** generation in the secondary beams at the K1.8BR. (J-PARC News)





**For more details,**

**Please ask to the machine staff at J-PARC**

**Thank you for your attention !!**